



Infrastructure · Water · Environment · Buildings

Richard Nussbaum, P.E., R.G.
Chief, Permits Section – Hazardous Waste Program
Missouri Department of Natural Resources
1738 Elm Street, P.O. Box 176
Jefferson City, MO 65102

Patricia A. Murrow
U.S. Environmental Protection Agency, Region VII
AWMD/RCAP
901 North 5th Street
Kansas City, Kansas 66101

Subject:

Submittal of Interim Groundwater Remediation System Construction Complete Report
Formerly American Cyanamid Company Facility near Hannibal, Missouri
EPA ID Number MOD050226075

Dear Mr. Nussbaum and Ms. Murrow:

ARCADIS U.S., Inc. (ARCADIS) is submitting the Construction Completion Report for the interim groundwater remediation system at the above referenced facility. Copies have been submitted to both the Missouri Department of Natural Resources (MDNR) and the Environmental Protection Agency (EPA).

If you have any questions regarding the enclosed information, please contact John Shonfelt of ARCADIS at 913.492.0900, extension 11.

Sincerely,

ARCADIS U.S., Inc.

John P. Shonfelt
Senior Project Manager/Hydrogeologist

cc: Mike Dandurand, MDNR
Curt Gardner, BASF
William Winkley, Wyeth

RCAP-RECEIVED

JUL 08 2011

ARCADIS U.S., Inc.
8725 Rosehill
Suite 350
Lenexa
Kansas 66215
Tel 913 492 0900
Fax 913 492 0902

ENVIRONMENTAL

Date:
7 July 2011

Contact:
John P. Shonfelt

Phone:
913.492.0900

Email:
john.shonfelt@arcadis-us.com

Our ref:
KC001589.0001

Imagine the result

510600



RCRA



Infrastructure · Water · Environment · Buildings

Imagine the result

Former American Cyanamid Company

**Construction Completion Report
for
Groundwater Recovery and
Treatment System**

Agricultural Products Division Facility

Hannibal, Missouri

EPA ID No. MOD050226075

06 July 2011

RCAP RECEIVED


JUL 08 2011



Bretton C. Overholtzer, P.E.
Senior Engineer

Royce A. Face, P.E.
Senior Engineer

John P. Shonfelt
Senior Project Manager



7/6/11

Construction Completion Report

Groundwater Recovery and
Treatment System

Prepared for:

Former American Cyanamid Company
Agricultural Products Division Facility
Hannibal, Missouri

Prepared by:

ARCADIS U.S., Inc.
Rosehill Office Park 1
8725 Rosehill
Suite 350
Lenexa
Kansas 66215
Tel 913 492 0900
Fax 913 492 0902

Our Ref.:

KC001575.0001

Date:

July 6, 2011

This document is intended only for the use of the individual or entity for which it was prepared and may contain information that is privileged, confidential and exempt from disclosure under applicable law. Any dissemination, distribution or copying of this document is strictly prohibited.

1. Introduction	1
1.1 Site Location and Description	1
1.2 Regulatory History and Background	1
2. Remedial Construction	3
2.1 Site Access and Security	4
2.2 Site Preparation	4
2.3 Groundwater Recovery and Treatment System	5
2.3.1 General Processes	5
2.3.2 System Design Modifications	6
2.3.3 Treatment Building	7
2.3.4 Recovery Wells and Piping	7
2.3.5 Process Equipment	8
2.3.5.1 Groundwater Recovery Pumps	8
2.3.5.2 Air Stripper and Blowers	9
2.3.5.3 Sequestering Agent	9
2.3.5.4 Liquid Phase Granular Activated Carbon Units	9
2.3.5.5 In-line Gas Chromatograph	10
2.3.5.6 Clean-in-Place System	10
2.4 Utility Service	10
2.5 Site Grading and Cover	11
2.6 As-Built Survey	11
3. Operating Permit	12
4. References	13

Figures

- 1 Site Location Map

Appendices

- A Record Drawings
- B Construction Photographic Log
- C As-Built Survey – Piping and Primary Structures
- D Recovery Well Completion Logs

1. Introduction

ARCADIS, on behalf of Wyeth Holdings Corporation (a division of Pfizer Inc.) has prepared this Final Construction Completion Report for the Interim Groundwater Corrective Measure implemented at the Agriculture Products Facility (the Site or Facility) near Hannibal, Missouri (Figure 1). This report summarizes the final engineering design and construction activities associated with implementation of interim measures, and includes "as-built" Record Drawings (Appendix A) for the groundwater extraction and treatment system.

1.1 Site Location and Description

The Facility is situated on approximately 2,200 acres of land on the west bank of the Mississippi River. The site is located along Route JJ in Marion County, approximately 10 miles northwest of Hannibal, Missouri and five miles southwest of Quincy, Illinois. The Site is located in Sections 10, 11, 14, 15, 22, and 23 Township 3 South, Range 5 West and at latitude 91°27'45" and longitude 39°51'10" (Figure 1). Approximately 250 acres are currently used for the active processing and manufacturing of agricultural chemicals and associated plant support operations. The remaining land is used for flood protection levees and typical agricultural purposes.

The Facility is currently engaged in the manufacturing of agricultural products including herbicides and insecticides. The Facility is currently owned and operated by BASF Corporation; however, Pfizer (formerly Wyeth) and Wyeth Holdings Corporation (jointly Wyeth) retain contractual responsibility for certain historical environmental matters.

1.2 Regulatory History and Background

This Construction Completion Report summarizes the installation of the groundwater extraction and treatment system (the System) and has been prepared to satisfy a requirement contained in the Interim Groundwater Corrective Measures Work Plan (ARCADIS, 2008) which was prepared pursuant to the Hazardous Waste Management Facility Permit (Permit # MOD0226075) issued by the Missouri Department of Natural Resources (MDNR) and the Hazardous and Solid Waste Amendments (HSWA) Permit issued by the U.S. Environmental Protection Agency (USEPA) on April 25, 1990, to the American Cyanamid Company.

A letter from USEPA, dated September 19, 2007, approved the Resource Conservation and Recovery Act (RCRA) Facility Investigation (RFI) Report (ARCADIS, 2005) and the Phase II RFI (ARCADIS, 2006) and directed Wyeth to prepare a Corrective Measures Study (CMS) Work Plan in accordance with Section III of the Facility's RCRA Hazardous Waste HSWA Permit. However, changes in hydraulic conditions at the Site and plans by BASF to implement new industrial water supply wells in 2008 necessitated the need to install an Interim Groundwater Corrective Measure concurrent with the expansion of the Plant's water supply system.

Several documents were developed and submitted to the MDNR to justify and provide rationale for the implementation of the Interim Groundwater Corrective Measure at the site, including:

- Interim Groundwater Corrective Measure Work Plan, dated June 6, 2008 – presented the treatment system design, system operations, performance monitoring and initial modeling used to locate the extraction wells. (Approved by MDNR in a letter dated July 12, 2008);
- Additional Groundwater Delineation and Capture Zone Modeling Documentation Report, dated January 16, 2009 – presented the results of the additional groundwater sampling and subsequent capture zone modeling that was performed to assess the impacts of the 2008 Mississippi River flooding on the distribution of impacted groundwater beneath the facility. (Approved by MDNR in letter dated February 6, 2009); and
- 90 Percent Design, Interim Groundwater Corrective Measures, dated February 26, 2009 – presented the nearly-complete design package for the groundwater extraction and treatment system. The 90-percent design incorporated an additional recovery well and changes to well locations brought about by a review of the additional groundwater modeling performed in the 4th Quarter of 2008. (Approved by MDNR in letter dated April 7, 2009).

2. Remedial Construction

Construction began on the treatment system on November 30, 2009, with equipment mobilization and project safety briefing for the on-site contractors. Major construction milestones included:

- November 30 to December 7, 2009 – drilled and installed recovery wells.
- December 2009 to April, 2010 – cleared utilities with air knifing, excavated trench and installed piping to recovery wells.
- Late December 2009 to February 2010 – prepared building footings and floor slab.
- February/March 2010 – constructed building lower walls, iron framework, roof, walls, and doors. Building complete by late-March 2010.
- Mid-April, 2010 – treatment equipment delivered to building.
- Late April, 2010 - well vaults formed and poured.
- April/May, 2010 - install treatment system equipment in building.
- May 27, 2010 – system substantially complete – Initial punch list prepared.
- June and July, 2010 – system testing and shakedown operation.
- Late July, 2010 – system placed into operation at half-capacity.
- September 29-30, 2010 – piping modifications performed on the air intake to provide separate air source to each stripper.
- October 20-22, 2010 – piping modifications and pump installation to provide a separate sump discharge pump to each air stripper.
- December, 2010 – installation of granulated activated carbon (GAC) vessels and piping modifications to install header and connect vessels to discharge piping.

- February, 2011 – installation of Inficon gas chromatograph, remote data access, and installation of slip-stream water line to Inficon. Inficon system setup and calibration.
- May, 2011 – evaluation of sequestrant effectiveness, and proposed revisions to address greater than anticipated iron concentrations in the raw water.

Construction photos are presented in Appendix B.

2.1 Site Access and Security

During construction, access to and from the construction zones were restricted to contractors, ARCADIS staff, and BASF plant employees, as needed. The Facility is restricted to plant employees and visitors of the plant. All on-site staff and visitors were noted on the daily construction activities report. Contractors and visitors (if any) were logged by the On-site Safety Officer and were required to sign a visitor's log sheet, which is part of the Site Health and Safety Plan.

Although mobile phones are not allowed at the BASF Facility, the treatment building is located outside of the fenced area, where mobile phones are allowed. A Safety Work Permit was required each morning from BASF.

While the treatment building and active treatment components are predominantly located outside the active and fenced-in portion of the Facility, site security is provided by plant personnel and in-place procedures. The treatment building is locked when not occupied. Vehicle access to the treatment building is via a chained gate crossing the road.

2.2 Site Preparation

Prior to commencing intrusive activities, all well locations, the treatment building locations, and the piping trench locations were discussed and approved by BASF engineering staff. Existing plant utility maps were reviewed to locate any known utilities prior to trenching. In addition, all trenching within the plant boundaries was preceded by air knifing to a depth of 4 ft. to expose any known and unknown plant piping, conduits, or wiring.

Outside the plant fence, air knifing was used to locate and clear known utilities as they were identified from one-call or local utility companies.

2.3 Groundwater Recovery and Treatment System

The groundwater recovery and treatment system was designed and built to extract and treat groundwater impacted by 1,2-dichloroethane (DCA), and monochlorobenzene (MCB) at the Facility. The locations and pumping rates of the recovery wells were identified using computer modeling to provide hydraulic capture of the impacted groundwater under varying river stages, groundwater levels, and plant water well pumping conditions. The initial numerical modeling was presented in the MDNR-approved Interim Groundwater Corrective Measures Work Plan (ARCADIS, 2008). After the 2008 Mississippi River flooding, additional numerical modeling was performed to evaluate the impact of high water levels on the impacted groundwater plume. The flood-impacted groundwater modeling was summarized in the MDNR-approved Additional Groundwater Delineation and Capture Zone Modeling Documentation (ARCADIS, 2009a). Based on an evaluation of the flood-impacted modeling results, an additional recovery well was added to the System, and well locations were moved to optimally achieve capture of the plume. The additional well and revised well locations were reflected in the MDNR-approved 90 Percent Design document (ARCADIS, 2009b).

The as-built groundwater recovery and treatment system layout is shown on Drawings PID1, PID2, and PID2A in Appendix A.

2.3.1 General Processes

The system consists of three recovery wells pumping water to a treatment building, with treated water discharged to a borrow ditch. The sequence of treatment within the system is visually presented in the schematic process flow diagrams (PID1, PID2, and PID3 in Appendix A).

Groundwater is extracted from the aquifer by the extraction wells, and is conveyed via underground piping to the treatment building. At the treatment building, the flow is metered and a dose of sequestrant/chelating chemical is automatically mixed with the raw influent to prevent iron, calcium, and manganese from precipitating out of solution in the form of scale or sludge. The water stream is then split and pumped through two air strippers in parallel. Counter-current air is delivered to each air stripper to volatilize the dissolved phase compounds of concern (COC). Treated water is collected in the effluent sump of each air stripper. The treated water is pumped from the sumps to the GAC vessels for secondary treatment.

The 5,000 lb GAC vessels are operated in a lead-lag fashion to provide initial and polishing treatment. A slip-stream of water is collected from after the first GAC vessel and run through the in-line gas chromatograph for on-Site analysis. The treated effluent is then delivered to the NPDES-permitted point of discharge located in a borrow ditch south of the Facility. Vapor from the air strippers vent through mist eliminators to the atmosphere.

Remote system monitoring is achieved through a cellular modem connected to the programmable logic controller (PLC) that transmits System parameters to the server maintained by the equipment vendor (MLEE). The system can be monitored and operated via remote access. Additionally, operational data, such as pumping rates and air stripper back pressures, is logged and can be accessed via remote monitoring.

The alarm component of the PLC monitors system operation and sends out text messages and emails when alarm conditions occur. In addition, when certain alarm conditions are met, the PLC is designed to shut down the system automatically. Both hard (non-recoverable – system will shut down) and soft (recoverable – system will continue to operate) alarms trigger notification.

2.3.2 System Design Modifications

The system was placed into operation in late-June 2010. After approximately two months of operation at half capacity, carbonate and iron fouling of the air stripper trays was reported which reduced the treatment efficiency of the air strippers. The air stripper trays were cleaned and an evaluation was performed to determine the causes of deterioration of treatment efficiency. The system evaluation resulted in several modifications , including:

- Re-configuring the air intake piping to provide a separate air pathway to each stripper
- Re-configuring the stripper treated water discharge to provide separate stripper sump pumps.

The piping was modified in September and October 2010 to incorporate these revisions to the treatment system.

In order to provide an additional level of polishing treatment prior to discharge to the NPDES outfall, two GAC vessels were installed downstream of the air strippers in December 2010. The GAC vessels operate in series, and a piping header allows flexibility during operation and backwashing.

Additionally, a mobile gas chromatograph (GC) was installed at the treatment building to provide additional confirmation that treatment levels are being achieved. A low-flow slip stream of water is extraction from the treatment discharge piping after the lead GAC vessel and prior to the second GAC vessel. The slip-stream water is analyzed hourly by the GC for the NPDES constituents (except for 1,1,2-Trichloroethane, which is not on the standard Inficon method list). The GC is configured to send an alarm to the PLC if concentrations of NPDES parameters are reported above pre-set levels. The pre-set levels that trigger alarms are generally one-half to one-tenth the NPDES-permitted levels.

2.3.3 Treatment Building

The treatment equipment is housed in a 30 ft by 30 ft pre-engineered treatment building, which includes the following features:

- Dual garage door-style roll-up openings that accommodate equipment delivery and maintenance of the shallow tray strippers
- Industrial concrete flooring with integral spill containment around the building perimeter
- Floor sump with high level switch. Any water that accumulates in the sump is processed through the air stripper.
- Thermostatically-controlled electrical convection heaters
- Incandescent lighting with vapor tight globe and wall switch

2.3.4 Recovery Wells and Piping

The three extraction wells are designed to pump at flow rates of 40 to 60 gallons per minute (gpm) each. The target operational flow rates, based on modeling simulations, include:

- RW-1 (south well) – 60 gpm
- RW-2 (north well) – 50 gpm
- RW-3 (west well) – 40 gpm

The wellhead and local discharge piping are installed in below-grade pre-cast concrete access vaults. The access vaults have locked, flush-mounted, watertight, and hinged access lids. A shut off valve and pressure gauge are located in the discharge piping within each wellhead access vault. Power wiring is routed to an electrical disconnect junction box above the well vault. The piping within each well and the wellhead access vault is galvanized carbon steel which transitions to high-density polyethylene (HDPE) double-wall piping within the access vault. Well completion diagrams for the three recovery wells are included in Appendix D.

Conveyance piping is constructed of double-walled high-density polyethylene (HDPE) pipe (2-inch diameter for the inner piping and 4-inch diameter for the secondary containment piping) from the extraction well vaults to the treatment building. The conveyance piping transitions to single-walled piping in the treatment building. A single-walled 1-inch recirculation line from the treatment building to each well is included. This recirculation line will be used during piping maintenance to remove scaling in the conveyance piping if pressure losses interfere with system operation. The treated water discharge piping to the outfall is single-walled.

2.3.5 Process Equipment

The following sections provide a brief overview of the major components of the treatment system.

2.3.5.1 Groundwater Recovery Pumps

The groundwater recovery pumps are conventional, submersible multi-stage water well-type pumps. The electrical pump motors use 230V, 1-phase electrical service. The pumps are located near the top of each well's screened interval, with the intake at approximately 40 ft below ground surface (bgs).

Flow rate adjustments can be made by a manual throttling valve located downstream of the flow meter in the treatment building. Pressure gauges are installed at the well head and in the treatment building to monitor conveyance pipeline loss.

2.3.5.2 Air Stripper and Blowers

The air stripping equipment consists of two shallow tray air strippers (QED EZ-tray model 24.6). Each stripper has six trays that can be removed for cleaning. The strippers are made of stainless steel, with a footprint of 6 ft deep by 5 ft wide and 9 ft tall.

A piping manifold combines the flow from the three recovery wells, and then splits the combined flow, directing half the raw influent to each stripper. Following treatment, the water from each stripper sump is combined and passes through post-stripper bag filters before passing through the GAC treatment vessels for final treatment.

2.3.5.3 Sequestering Agent

Mineral sequestering treatment is implemented to prevent minerals, such as iron, manganese, or hardness from adversely impacting the operation of the System. Mineral precipitation is minimized by injecting a chemical additive to the combined raw influent prior to the air stripping treatment. Two separate sequestrant formulations are used: one sequestrant to address carbonate scaling and a second formation to address iron in the raw water. The selected sequestrants are delivered to the site in 55-gallon drums are mixed with water (to reduce viscosity) in sequestrant storage totes. Chemical feed pumps deliver the sequestrant agents into the raw water line at the desired feed dosages.

As described in the Interim Measures Work Plan (ARCADIS, 2008) the effectiveness of the sequestrant was evaluated after initial operation. After the System had been operating for several months, the influent concentration of iron increased dramatically, and a sequestrant evaluation was performed to respond to the changed conditions. The types and dosages of sequestrant were revised to disperse the iron and maintain System operation. The impact of the observed influent iron concentration on System operations will be evaluated regularly as part of the System operation and maintenance (O&M) activities.

2.3.5.4 Liquid Phase Granular Activated Carbon Units

Two steel GAC vessels, each containing 5,000 lbs of activated carbon, have been installed at the treatment building. Water from the air stripper sumps are directed through bag filters prior to entering the GAC vessels. The GAC vessels are arranged

in a 'lead-lag' arrangement, with the combined effluent flow passing through each vessel in series.

The GAC vessels are constructed of carbon steel, 6 ft diameter, approximately 10 ft tall, and have a volume of 1,326 gallons each. The carbon is virgin grade, coconut hull liquid phase carbon (8 x 30 mesh).

2.3.5.5 In-line Gas Chromatograph

An Inficon model CMS5000 in-line Gas Chromatograph was installed in early 2011. The CMS5000 Monitoring System is a self-contained system utilizing GC technology for continuous, unattended remote monitoring and analysis of water. During operation, a continuous slip-stream of water is provided to the system, and a grab sample is picked off the slip-stream approximately hourly. Water samples are analyzed for the primary NPDES parameters, and results stored in the on-site database for subsequent review. Alarm points are set for the parameters and an alarm signal is sent to the treatment system PLC and subsequently transmitted to the operators via text messaging and email. The pumping and treatment system will shut down operation if the In-line gas chromatograph senses water concentration above the alarm set points.

2.3.5.6 Clean-in-Place System

The System was constructed with 1-inch diameter recirculation lines extending from the treatment building to each extraction well, as well as acid circulation piping within the treatment building to the air strippers. Unacid acid (or equivalent) will be delivered in granular or powder form and introduced to the 500-gallon clean-in-place tank. The clean-in-place pump is used to convey cleaning water to the wells, treatment system piping, and air strippers.

2.4 Utility Service

Electrical service to the Site was obtained through the construction of new power feed line from an electrical substation located approximately one mile north of the treatment building. Overhead lines convey power from the substation to a utility pole approximately 600 ft south of the treatment building. Power is transferred via underground conduit from the utility pole to a transformer located on the west side of the treatment building. A 480 volt, three phase, 45KVA electrical service was installed to satisfy the power requirements of the groundwater recovery and treatment system.

A power disconnect is located at the main power panel in the building in case of emergency.

Water service is provided by Marion County Public Water. A water distribution line exists approximately 200 feet south of the treatment building. A water meter was installed at this location and the water service placed in the RW-1 piping trench to the building.

The system PLC and Inficon gas chromatograph PC connection use cellular data service to transmit information for the remote telemetry control/monitoring and analytical data acquisition.

2.5 Site Grading and Cover

Upon completing all site-related construction activities, the area surrounding the treatment building was graded and gravel placed to prevent erosion and match pre-construction conditions. Areas disturbed by the installation of piping were graded to match the existing ground surface and graveled where appropriate. Several paved areas that were disturbed during construction were patched with asphalt. The well vault areas were graded to achieve drainage, and covered with gravel to prevent erosion.

2.6 As-Built Survey

As specified in the Interim Groundwater Corrective Measures Work Plan (ARCADIS, 2008), a professional engineer was employed to survey the 'as-built' locations of the treatment building, recovery well locations, piping cleanout and electrical pull box locations, trench locations, and locations of other major system components. The northing and easting coordinates are tied-into the original plant coordinate system, consistent with previously installed monitoring wells at the site. The as-built survey is presented in Appendix C.

3. Operating Permit

A Missouri State Operating Permit, permit number MO-0135765, was obtained to discharge treated effluent from the extraction and treatment system. The operating permit was issued in compliance with the Missouri Clean Water Law (Chapter 644 R.S. MO) and the Federal Water Pollution Control Act, and sets effluent limits and monitoring requirements for the extraction and treatment system.

The single outfall (001) is located at a borrow ditch approximately 800 ft southwest of the treatment building.

4. References

ARCADIS, 2005. RCRA Facility Investigation Report. Former American Cyanamid Company Agricultural Products Division Facility, Hannibal, Missouri. ARCADIS U.S., Inc. Lenexa, Kansas.

ARCADIS, 2006. Phase II RCRA Facility Investigation Report. Former American Cyanamid Company Agricultural Products Division Facility, Hannibal, Missouri. ARCADIS U.S., Inc. Lenexa, Kansas. October.


ARCADIS, 2008. Interim Groundwater Corrective Measures Work Plan. Former American Cyanamid Company, Agricultural Products Facility. Hannibal, Missouri. EPA ID No. MOD050226075. ARCADIS U.S., Inc. Lenexa, Kansas. June 6.

ARCADIS, 2009a. Additional Groundwater Delineation and Capture Zone Modeling Documentation Report. Former American Cyanamid Company. Agricultural Products Facility. Hannibal Missouri. EPA ID No. NOD050226075. ARCADIS U.S., Inc. Lenexa, Kansas. February 26.

ARCADIS, 2009b. 90 Percent Design Interim Groundwater Corrective Measures. Former American Cyanamid Company. Agricultural Products Facility. Hannibal Missouri. EPA ID No. NOD050226075. ARCADIS U.S., Inc. Lenexa, Kansas. February 26.

ARCADIS, 2010. Operation and Maintenance Manual for Groundwater Extraction and Treatment System. Former American Cyanamid Company, Agricultural Products Facility. Hannibal, Missouri. EPA ID No. MOD050226075. ARCADIS. Lenexa, Kansas. July 29.

Figures



6720 S. BROADWAY, STE. 300
 HANNIBAL, MISSOURI 64301
 TEL (314) 482-4000 FAX (314) 482-4002

0 1500 FT.

SITE LOCATION MAP

FORMER AMERICAN CYANAMID COMPANY
 AGRICULTURAL PRODUCTS FACILITY
 HANNIBAL, MISSOURI

PROJECT NUMBER
 KC001475.0001

FIGURE NUMBER

1



Appendix A

Record Drawings

RECORD DRAWINGS

WYETH GROUNDWATER TREATMENT SYSTEM

KEY CONTACTS:

PROJECT SITE:
WYETH HOLDINGS CORPORATION
FORMER AMERICAN CYANAMID
GROUNDWATER TREATMENT SYSTEM
3150 HIGHWAY JJ
PALMYRA, MISSOURI 63461
TELEPHONE: 973.660.5000
CONTACT: WILLIAM B. WINKLEY


OWNER:
WYETH HOLDINGS CORPORATION
5 GIRALDA FARMS
MADISON, NEW JERSEY 07940
TELEPHONE: 973.660.5000
CONTACT: WILLIAM B. WINKLEY

ENGINEER:
ARCADIS U.S., INC.
8725 ROSEHILL
SUITE 350
LENEXA, KANSAS 66215
TELEPHONE: 913.492.0900
CONTACT: BRET OVERHOLTZER



SURVEYOR:
MECO ENGINEERING COMPANY, INC.
3120 HIGHWAY W
HANNIBAL, MISSOURI 63401
(573) 221-4048
CONTACT: KEVIN BOCK

INDEX TO DRAWINGS

		REVISION NUMBER AND DATE
CIVIL		
C1	SITE LAYOUT PLAN	RO (7-21-09)
C2	PIPING AND TRENCHING DETAILS	RO (7-21-09)
C3	DISCHARGE OUTFALL DETAILS	RO (7-21-09)
HVAC		
H1	TREATMENT BUILDING HVAC PLANS, LEGEND & NOTES	RO (7-21-09)
H2	TREATMENT BUILDING HVAC SCHEDULES, SPECIFICATIONS & DETAILS	RO (7-21-09)
STRUCTURAL		
S1	STRUCTURAL NOTES	RO (7-21-09)
S2	BUILDING ELEVATIONS	RO (7-21-09)
S3	FOUNDATION PLAN	RO (7-21-09)
S4	FLOOR PLAN	RO (7-21-09)
S5	SECTIONS AND DETAILS	RO (7-21-09)
PROCESS		
PID1	PIPING AND INSTRUMENTATION DIAGRAM	R1 (5-11)
PID2	PIPING AND INSTRUMENTATION DIAGRAM	R1 (5-11)
PID2A	PIPING AND INSTRUMENTATION DIAGRAM	R1 (5-11)
PID3	PIPING AND INSTRUMENTATION DIAGRAM DETAILS SHEET	R1 (5-11)
MECHANICAL		
M1	TREATMENT BUILDING LAYOUT	R1 (5-11)
M2	TREATMENT BUILDING SECTIONS	R1 (5-11)
M3	TREATMENT BUILDING SECTIONS	R1 (5-11)
M4	MECHANICAL DETAILS	R1 (5-11)
M5	EXTRACTION WELL AND VAULT CONSTRUCTION DETAILS	R1 (5-11)
ELECTRICAL AND CONTROLS		
E1	ELECTRICAL SITE PLAN	R1 (5-11)
E2	ELECTRICAL LAYOUT	R1 (5-11)
E3	SINGLE LINE DIAGRAM	RO (7-21-09)
E4	ELECTRIC SCHEDULES	RO (7-21-09)
E5	LOGIC DESCRIPTION	RO (7-21-09)



REFERENCE: BASE MAP USGS 7.5 MINUTE QUADRANGLE, QUINCY SW, MO-IL, 1996.




DATE ISSUED
MAY 2011

WYETH HOLDINGS CORPORATION
HANNIBAL, MISSOURI



ARCADIS U.S., INC.

CITY: DIVGROUP: DB: LD: PIC: PM: LVRON=OFF=REF- C:\Documents and Settings\ldon\Desktop\Civil-C-1 Site Layout Plan.dwg LAYOUT: C1 SAVED: 2/26/2009 5:48 AM ACADVER: 17.05 (LMS TECH) PAGESETUP: PLOTSTYLETABLE: BLACKGRAY-THIN.CTB PLOTTED: 2/26/2009 5:48 AM BY: DORN, RYAN



CITY: DIVGROUP: DB: LD: PIC: PM: LYNON+ OFF=REF*
G:\PROJECTS\Wyeth\Design\Arch\Structural\H1 - HVAC Plans.dwg LAYOUT: H1 SAVED: 6/23/2009 2:23 PM ACADVER: 17.05 (LMS TECH) PAGES: 17 PLOTTED: 6/24/2009 10:36 AM BY: DORN, RYAN
XREFS: IMAGES: PROJECTNAME: ---

ELECTRIC UNIT HEATER DETAIL (TYP. FOR 4) SEE DETAIL A H1/H2

EUH-3 MOUNT
BOTTOM 8'-0" AFF

PROPELLER EXHAUST FAN DETAIL (TYP. FOR 1) SEE DETAIL B H1/H2

TO EMC FOR EF-1

EF-1: MOUNT
BOTTOM 11'-0" AFF

18'-5"

EUH-2: MOUNT
BOTTOM 8'-0" AFF

LOUVER/DAMPER DETAIL (TYP. FOR 2) SEE DETAIL C H1/H2

L-1: MOUNT TOP
7'-4" AFF

L-2: MOUNT TOP
7'-4" AFF

EUH-4 MOUNT
BOTTOM 8'-0" AFF

EUH-1: MOUNT
BOTTOM 8'-0" AFF



HVAC LEGEND

- EF EXHAUST FAN
- EUH ELECTRIC UNIT HEATER
- L LOUVER
- ① THERMOSTAT

GENERAL/HVAC NOTES

- DO NOT SCALE DRAWINGS. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE APPROXIMATE LOCATION OF HVAC EQUIPMENT. THE CONTRACTOR SHALL COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS AND DELAYS. MINOR OFFSETS AND ADJUSTMENTS SHALL BE PROVIDED WHERE REQUIRED AT NO ADDITIONAL COST TO THE OWNER. DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.
- WHEREVER THE WORD "PROVIDE" IS USED, IT SHALL MEAN "FURNISH AND INSTALL COMPLETE AND READY FOR USE."
- THERMOSTATS SHALL BE LOCATED 48" AFF UNLESS OTHERWISE NOTED. ALL CONDUIT, ROUGH IN ELECTRICAL BOXES AND WIRING, EXCLUDING LOW VOLTAGE CONTROL WIRING, SHALL BE INCLUDED UNDER THE ELECTRICAL SECTION OF THE CONTRACT DOCUMENTS. COORDINATE REQUIREMENTS AND ROUGH IN LOCATION FOR ALL CONTROL DEVICES, ELECTRICAL CONNECTIONS TO EQUIPMENT, AND SWITCH LOCATION. CONTROL WIRING SHALL BE PROVIDED AND INSTALLED UNDER THE HVAC SECTION OF THE CONTRACT DOCUMENTS.
- INSTALL ALL HVAC EQUIPMENT AND APPURTENANCES IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, CONTRACT DOCUMENTS, AND APPLICABLE CODE REQUIREMENTS AND REGULATIONS. ALL EQUIPMENT IS TO BE INSTALLED WITH MANUFACTURER'S RECOMMENDED CLEARANCES AND REQUIRED ACCESS.
- PROVIDE A MINIMUM OF 10' CLEARANCE BETWEEN FRESH AIR INTAKES AND EXHAUST OUTLETS.
- ALL OF THE COSTS ASSOCIATED WITH PROVIDING TEMPORARY HEATING AND VENTILATION SHALL BE BORNE SOLELY BY THE CONTRACTOR, INCLUDING BUT NOT LIMITED TO POWER CONSUMPTION AND EQUIPMENT CLEANING.
- COORDINATE CONSTRUCTION OF ALL HVAC WORK WITH ARCHITECTURAL, STRUCTURAL, CIVIL, ELECTRICAL WORK, ETC., SHOWN ON OTHER CONTRACT DOCUMENTS. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL EQUIPMENT ELECTRICAL CHARACTERISTICS WITH THE ELECTRICAL SERVICE AND THE ELECTRICAL CONTRACTOR. THE SCOPE OF THIS COORDINATION IS, BUT NOT LIMITED TO: COORDINATE VOLTAGE, PHASE, AMP CAPACITY, WIRE SIZE, CONDUIT SIZE AND LOCATION, DISCONNECT SIZE AND LOCATION, FUSE SIZE, ETC. OF ALL EQUIPMENT. IN THE EVENT OF A CONFLICT, THE HVAC CONTRACTOR IS TO NOTIFY THE ENGINEER PRIOR TO HVAC AND ELECTRICAL EQUIPMENT BEING ORDERED. ALL CONTROL WIRE AND CONDUIT SHALL COMPLY WITH THE NATIONAL ELECTRIC CODE.
- THE CONTRACTOR SHALL PROVIDE ALL LABOR, MATERIALS, EQUIPMENT, CONTROL SYSTEMS, DEVICES, PERMITS AND SERVICES NECESSARY FOR FURNISHING AND INSTALLING A COMPLETE OPERABLE HVAC SYSTEM AS INDICATED ON THE DRAWINGS, AS SPECIFIED AND AS REQUIRED BY CODE.
- ALL CUTTING, PATCHING, STRUCTURAL STEEL, WEATHER PROOFING, PAINTING, AND WALL OPENINGS REQUIRED FOR THE INSTALLATION OF HVAC WORK, SHALL BE PROVIDED BY THE CONTRACTOR AT NO COST TO THE OWNER. AND BE COORDINATED WITH THE OTHER TRADES INVOLVED.
- PROVIDE VIBRATION ISOLATORS ON ALL HVAC EQUIPMENT. IF NOT SPECIFICALLY CALLED OUT, PROVIDE AS RECOMMENDED BY MANUFACTURER FOR QUIET OPERATION AND TO PREVENT TRANSMISSION OF VIBRATION TO BUILDING STRUCTURE.
- THE CONTRACTOR SHALL VERIFY EXISTING CONDITIONS PRIOR TO BIDDING, ORDERING, FABRICATION OR INSTALLATION OF MATERIALS OR EQUIPMENT.
- TESTING, ADJUSTING, AND BALANCING CONTRACTOR SHALL BALANCE EXHAUST FAN AIRFLOW AS INDICATED ON THE DRAWINGS. FAILURE TO NOTIFY HVAC ENGINEER OF DEFICIENCIES PRIOR TO COMPLETION OF TESTING, ADJUSTING, AND BALANCING WORK SHALL PLACE BURDEN OF ANY NECESSARY RETESTING COSTS WITH THE CONTRACTOR. SUBMIT TESTING, ADJUSTING, AND BALANCING REPORT TO THE HVAC ENGINEER FOR APPROVAL PRIOR TO BUILDING OCCUPANCY.
- GENERAL CONTRACTOR TO COORDINATE ALL DISCIPLINES. AFTER SHOP DRAWINGS ARE APPROVED AND PRIOR TO START OF WORK.

TREATMENT BUILDING HVAC PLAN

SCALE: 3/8"=1'-0"



ARCADIS U.S., INC.

TREATMENT BUILDING HVAC PLANS, LEGEND & NOTES


HVAC

ARCADIS Project No.
KC001566.0001.0150
Date
FEBRUARY 26, 2009
ARCADIS U.S., INC.
8725 ROSEHILL
SUITE 350
LENEXA, KANSAS
TEL. 913.492.0900


H1

[illegible]

CITY: DIVGROUP. DB: LD: PIC: PM: LVR ON=OFF=REF-
G:\PROJECTS\WYETH\Design Drawings\Structural\3 - Foundation Plan.dwg
LAYOUT: S3 SAVED: 6/23/2009 1:48 PM ACADVER: 17.05 (LMS TECH) PAGES: 17 OF 17 PLOT: 6/24/2009 10:40 AM BY: DORN, RYAN
XREFS: IMAGES: PROJECTNAME: ---




PLAN DETAIL 1 (TYP. FOR 4)
SCALE: 1/2"=1'-0"




PLAN DETAIL 2 (TYP. FOR 4)
SCALE: 1/2"=1'-0"


NOTE: FOUNDATION DETAILS AND DIMENSIONS TO BE VERIFIED BASED ON BUILDING MANUFACTURER'S APPROVED SHOP DRAWINGS.




SECTION D
SCALE: 1/2"=1'-0"



ANCHOR BOLT DETAIL
NOT TO SCALE



PLAN DETAIL 3
SCALE: 1/2"=1'-0"



FOUNDATION PLAN
SCALE: 3/8"=1'-0"



WYETH HOLDINGS CORPORATION • HANNIBAL, MISSOURI
DESIGN / BID DRAWINGS


FOUNDATION PLAN

STRUCTURAL


ARCADIS Project No.
KC001566.0001.0150
Date
FEBRUARY 26, 2009
ARCADIS U.S., INC.
8725 ROSEHILL
SUITE 350
LENEXA, KANSAS
TEL: 913.492.0900

S3


CITY: DIV/GROUP: DB: LD: PIC: PM: T.M. LYNCH**OFF**REF**
G:\PROJECTS\WYETH\Design Drawings\Arch_S4 - Floor Plan.dwg LAYOUT: S4 SAVED: 6/23/2009 2:15 PM ACADVER: 17.05 (LMS TECH) PAGES: 17 OF 17 PLOTTED: 6/24/2009 10:40 AM BY: DORN, RYAN
XREFS: IMAGES: PROJECTNAME: S4



B SUMP SECTION
S3 S4 S4 SCALE: 1/2"=1'-0"



E GRATING SUPPORT DETAIL (TYP. FOR 4)
S4 S4 NOT TO SCALE



FLOOR PLAN
SCALE: 3/8"=1'-0"

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.		USE TO VERIFY FIGURE REPRODUCTION SCALE	
0	02/26/09	ISSUED FOR BID	
No.	Date	Revisions	By Ckd
THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.			







Professional Engineer's Name ROYCE FACE	
Professional Engineer's No. (PE NUM)	
State MO	Date Signed
Designed by RK	Project Mgr. BO
Drawn by RR	Checked by RK

ARCADIS
ARCADIS U.S., INC.


WYETH HOLDINGS CORPORATION • HANNIBAL, MISSOURI
DESIGN / BID DRAWINGS
FLOOR PLAN
STRUCTURAL

ARCADIS Project No.
KC001566.0001.0150
Date
FEBRUARY 26, 2009
ARCADIS U.S., INC.
8725 ROSEHILL
SUITE 350
LENEXA, KANSAS
TEL. 913.492.0900

S4


[illegible]


CITY: DIV/GROUP: DB: LD: PIC: PM: TM: LYRON-OFF=REF* C:\Users\seppanen\Desktop\As-Built Drawings\Wyeth PID.dwg LAYOUT: PID1
C:\Users\seppanen\Desktop\As-Built Drawings\Wyeth PID.dwg LAYOUT: PID1
PAGESETUP: 18.0S (LMS TECH) PAGES: 11X17 PDF PLOTSTYLETABLE: A-TEST-BLACKGRAY-THIN.CTB PLOTTED: 5/29/2011 8:43 AM BY: SEPPANEN, MAJIA




- INTERLOCKS**
- 1. HIGH LIQUID LEVEL IN AIR STRIPPER
GENERAL ALARM, SYSTEM TRIP (EXTRACTION PUMPS, AIR STRIPPER SKIDS, BLOWERS, MINERAL SEQUESTERING FEED SYSTEM, DISCHARGE PUMP, AND COLLECTION SUMP PUMP)
 - 2. CURRENT TO EXTRACTION PUMP OUTSIDE NORMAL RANGE
DISABLE INDIVIDUAL EXTRACTION PUMPS (CURRENT MONITOR TO BE LOCATED IN SYSTEM CONTROL PANEL)
- NOTES**
- 1) ALL INSTRUMENTS SHALL BE MOUNTED TO THE PIPING SYSTEM USING A TEE WITH APPROPRIATE BUSHINGS OR SADDLE-TYPE CONNECTIONS AND A TYPE 304 SS NIPPLE. DRILLED AND TAPPED CONNECTIONS ARE NOT ALLOWED.
 - 2) THE LAST VALVE NUMBER USED IS V-178.
 - 3) THE LAST LINE NUMBER USED IS 105.
- LEGEND**
- ② SKID-MOUNTED EQUIPMENT CONNECTIONS

SCALE(S) AS INDICATED		Professional Engineer's Name ROYCE FACE Professional Engineer's No. (PE NUM)		 ARCADIS ARCADIS U.S., INC.	WYETH HOLDINGS CORPORATION • HANNIBAL, MISSOURI DESIGN / BID DRAWINGS		ARCADIS Project No. KC001566.0001.0150		PID1
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.		USE TO VERIFY FIGURE REPRODUCTION SCALE			PIPING AND INSTRUMENTATION DIAGRAM		Date MAY 2011		
1 05/2011 RECORD DRAWINGS RD JF		0 07/21/09 ISSUED FOR BID RD JF					ARCADIS U.S., INC. 8725 ROSEHILL SUITE 350 LENEXA, KANSAS TEL. 913.492.0900		
No. Date Revisions		By Ckd			Designed by RD		Drawn by MS		




THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING:		USE TO VERIFY FIGURE REPRODUCTION SCALE	1a. <u>0/2/1/1/1</u> ISSUED FOR BID					RD	JP
			No. Date Revisions					By	Ckd
			THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.						
			MO		BO		ARCADIS U.S., INC.		
			Designed by RD		Drawn by MS		Checked by JF		PROCESS



- | | |
|----|---|
| UT | ARCADIS Project No.
KC001566.0001.0150 |
| | Date
MAY 2011 |
| | ARCADIS U.S., INC.
8725 ROSEHILL
SUITE 350
LENEXA, KANSAS
TEL. 913.492.0900 |

MECHANICAL




No.	Date	Revisions	By	C
THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME				

Y	Designed by RD	Drawn by MS	Checked by JF
---	-------------------	----------------	------------------




TREATMENT BUILDING LAYOUT

CITY: DIV/GRP. DB: LD: PIC: PM: LVR ONE" OFF="REF" G:\PROJECTS\WYETH\Design Drawings\Mechanical\M5 Well and Vault Construction Details.dwg LAYOUT: M5 SAVED: 6/23/2009 12:47 PM ACADVER: 17.05 (LMS TECH) PAGES: 17 OF 17 PLOT: 6/24/2009 10:49 AM BY: DORN, RYAN



GROUNDWATER EXTRACTION WELL DETAIL (TYP. OF 3)
NOT TO SCALE



GROUNDWATER EXTRACTION WELL VAULT PLAN (TYP. OF 3)
NOT TO SCALE

WELL CONSTRUCTION SCHEDULE (DEPTHS ARE FEET BELOW GRADE)

WELL ID	WELL TYPE	A	B	C	D	E	F	G	H	I	J
RW-1	GROUNDWATER EXTRACTION WELL	2.5	3.5	8	30	32	35	37	47	49	50
RW-2	GROUNDWATER EXTRACTION WELL	2.5	3.5	8	30	32	35	37	47	49	50
RW-3	GROUNDWATER EXTRACTION WELL	2.5	3.5	8	30	32	35	37	47	49	50

WELL CONSTRUCTION SPECIFICATIONS - GROUNDWATER EXTRACTION WELLS

WELL TYPE	WELL DIAMETER	SCREEN MATERIAL	SLOT SIZE	CASING MATERIAL	FILTER PACK	WELL SEAL	SURFACE COMPLETION
GROUNDWATER EXTRACTION WELL	8-INCH	STAINLESS STEEL WIRE-WRAPPED	40 SLOT	SCH. 80 PVC	MORIE #3	NEAT CEMENT	FLUSH MOUNT

SCALE(S) AS INDICATED

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.

USE TO VERIFY FIGURE REPRODUCTION SCALE

0 02/26/09 ISSUED FOR BID
No. Date Revisions
THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.

Professional Engineer's Name
ROYCE FACE
Professional Engineer's No.
(PE NUM)
State Date Signed Project Mgr.
MO BO
Designed by Drawn by Checked by
RD AT JF



ARCADIS U.S., INC.

WYETH HOLDINGS CORPORATION • HANNIBAL, MISSOURI
DESIGN / BID DOCUMENTS

EXTRACTION WELL AND VAULT CONSTRUCTION DETAILS

MECHANICAL

ARCADIS Project No.
KC001566.0001.0150


Date
FEBRUARY 26, 2009

ARCADIS U.S., INC.
8726 ROSEHILL
SUITE 350
LENEXA, KANSAS
TEL: 913.492.0900

M5



CITY: DIV/GRP: DB: LD: PIC: PM: T.M: LYN=OFF=REF-
G:\PROJECTS\Wyeth\Design Drawings\Electrical\E2 - Electrical Layout.dwg
LAYOUT: E2 SAVED: 6/23/2009 2:23 PM ACADVER: 17.05 (LMS TECH) PAGES: 17 PLOTTED: 6/24/2009 10:49 AM BY: DORN, RYAN
XREFS: IMAGES: PROJECTNAME: ----




DRAWING NOTES:

1. SEE DRAWING E-4 FOR CONDUIT/CONDUCTOR SCHEDULE, HVAC/LIGHTING SCHEDULE, AND PANEL PNL-2.
2. THE CONTRACTOR SHALL INSTALL A CABLE TRAY AROUND THE PERIMETER OF THE TREATMENT ROOM, FROM WHICH RIGID GALVANIZED CONDUIT DROPS SHALL ORIGINATE.
3. ELECTRICAL DRAWINGS ARE PARTIALLY DIAGRAMMATIC. REFER TO CIVIL, ARCHITECTURAL OR MECHANICAL DRAWINGS FOR GUIDANCE ON DIMENSIONS AND PRECISE LOCATIONS OF ELECTRICAL, INSTRUMENTATION OR CONTROL COMPONENTS. THE CONTRACTOR SHALL INSTALL THE ELECTRICAL SYSTEMS WITHOUT INTERFERING WITH THE DUCTS, PIPES, STRUCTURAL STEEL ETC. LIGHTING FIXTURES SHALL BE LOCATED SYMMETRICALLY IN PROPER RELATION TO FINISHED AREAS, EXCEPT WHERE DIMENTIONED DRAWINGS EXIST.
4. ALL CONDUITS ENTERING AND LEAVING SHEET METAL ENCLOSURES SHALL UTILIZE OIL-TIGHT CONDUIT HUBS FOR CONNECTION. HUBS SHALL BE MANUFACTURED BY THOMAS & BETTS, PANDUIT, OR APPROVED EQUIVALENT.
5. POWER, CONTROL AND INSTRUMENT UNDERGROUND FEEDS SHALL UTILIZE THE SAME TRENCH ROUTING AS THE WATER CONVEYANCE PIPES. ALL ELECTRICAL TRENCHES SHALL HAVE A MINIMUM OF 24" OF COVER, AND SHALL BE EQUIPPED WITH RED LOCATING/WARNING TAPE.
6. UNDERGROUND RACEWAYS SHALL BE OF PVC CONSTRUCTION, AND SHALL UTILIZE TPROCESS PIPING TRENCH AND ROUTING FOR INSTALLATION. CONDUITS SHALL MAINTAIN A MINIMUM OF 24" OF COVER AT ALL POINTS. ALL UNDERGROUND PVC CONDUIT SHALL TRANSITION TO RIGID GALVANIZED STEEL (R.G.S.) OR PVC-COATED R.G.S. AT LEAST 3 LINEAR FEET PRIOR TO PENETRATING UPWARD THROUGH GRADE.
7. CONTRACTOR SHALL INSTALL A GROUND LOOP CONSISTING OF STRANDED #2 AWG BARE COPPER CONDUCTOR, AND 3/4" X 10' GROUND RODS AT THE CORNERS. THE GROUND LOOP SHALL BE BONDED TO THE UTILITY GROUND BUS, AND ATTACHED TO THE BUILDING STRUCTURAL STEEL IN AT LEAST 2 LOCATIONS. ALL CONNECTIONS SHALL BE EXOTHERMIC.
8. ALL CONDUITS SHALL BE ROUTED OVERHEAD, UNLESS WRITTEN AUTHORIZATION TO DO OTHERWISE IS RECEIVED FROM THE ENGINEER. NO CONDUITS SHALL BE ROUTED ON GRADE.
9. ALL CONDUIT CONNECTIONS TO MOTORS, SENSORS OR OTHER INSTRUMENTATION SHALL UTILIZE LIQUIDTIGHT FLEXIBLE CONDUIT. FLEXIBLE CONNECTIONS SHALL BE BETWEEN 18" AND 36" IN LENGTH.
10. THE CONTRACTOR SHALL PROVIDE PULL BOXES IF REQUIRED TO ALLOW PULLING OF ALL CABLES AND CONDUCTORS WITHOUT DAMAGE.
11. ALL JUNCTION BOXES SHALL BE EQUIPPED WITH TERMINAL STRIPS FOR INSTALLATION OF CONNECTIONS. WIRE-NUTTED CONNECTIONS SHALL NOT BE PERMITTED IN INSTRUMENT OR CONTROL JUNCTION BOXES.
12. DISCONNECT SWITCHES, WHERE NOT INDICATED ON EQUIPMENT SHALL BE PROVIDED WHERE REQUIRED BY THE NEC.
13. SECURELY AND ELECTICALLY BOND ALL NON-CURRENT-CARRYING METALLIC PARTS OF STRUCTURES, ELECTRICAL EQUIPMENT AND RACEWAYS TO THE GROUNDING SYSTEMS INDICATED.

SKID NOTES:

1. CONTROLS AND INSTRUMENTS DEPICTED ON SKID ARE PRE-WIRED FROM JUNCTION BOX. CONTRACTOR SHALL ROUTE CABLES AND MAKE TERMINATIONS AT THE JUNCTION BOX.
2. INSTRUMENT BUBBLES CONTAINING A DOUBLE-OUTLINE CONSTITUTE THOSE PROVIDED AS A PRE-WIRED, INTEGRATED SKID, BY OTHERS. THE CONTRACTOR WILL PROVIDED WIRING CONNECTIONS BETWEEN THE MCP AND THE APPROPRIATE JUNCTION BOX MOUNTED ON EACH SKID. THE CONTRACTOR IS NOT RESPONSIBLE FOR MOUNTING THE INSTRUMENTATION INDICATED BY THE DOUBLE-OUTLINE, OR FOR CONDUIT OR WIRING BETWEEN THE INSTRUMENT AND THE ASSOCIATED FIELD JUNCTION BOX.



THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.

USE TO VERIFY FIGURE REPRODUCTION SCALE

No.	Date	Revisions	RD By	JF Ckd
0	02/26/09	ISSUED FOR BID		

THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.

Professional Engineer's Name ROYCE FACE	
Professional Engineer's No. (PE NUM)	
State MO	Date Signed
Designed by JS	Project Mgr. BO
Drawn by JS	Checked by JF

ARCADIS U.S., INC.

WYETH HOLDINGS CORPORATION • HANNIBAL, MISSOURI
DESIGN / BID DRAWINGS

ELECTRIC LAYOUT








ELECTRICAL



ARCADIS Project No. KC001566.0001.0150
Date FEBRUARY 26, 2009
ARCADIS U.S., INC. 8725 ROSEHILL SUITE 350 LENEXA, KANSAS TEL: 913.492.0900

E2

TREATMENT PLANT CONDUIT AND CONDUCTOR SCHEDULE							
CONDUIT #	SIZE	CONDUIT TYPE	CONDUCTOR SIZE AND TYPE	PURPOSE	ORIGINATION	TERMINATION	COMMENTS
P-1	3"	PVC	BY UTILITY	MAIN POWER FEEDER	SUB-STATION	T-1	SUPPLIED BY UTILITY
P-2	3"	PVC/R.G.S.	(3)#500 MCM THHN, (1)#2 GND	MAIN POWER FEEDER	T-1	PNL-1	SUPPLIED BY UTILITY
P-3	2"		(3)#2 AWG. THHN, (3)#3 AWG. THHN, (3)#8 AWG. THHN, (3)#12 GND	P-EW-1, P-EW-2, P-EW-3 POWER	PNL-1	JB-100	
P-4A,B	2"	PVC	(3)#2 AWG. THHN, (1)#12 GND	P-EW-1 POWER	JB-100	RW-1	MOTOR STARTER IN MCC (PNL-1)
P-5A,B	2"	PVC	(3)#4 AWG. THHN, (1)#12 GND	P-EW-2 POWER	JB-100	RW-2	MOTOR STARTER IN MCC (PNL-1)
P-6A,B	2"	PVC	(3)#8 AWG. THHN, (1)#12 GND	P-EW-3 POWER	JB-100	RW-3	MOTOR STARTER IN MCC (PNL-1)
P-7	NA	NA	(3)#8 AWG. THHN, (1)#10 GND	T-1 FEEDER	PNL-1	T-1	LOCATED INSIDE MCC
P-8	NA	NA	(3)#3 AWG. THHN, (1)#8 GND	PNL-2 FEEDER	T-2	PNL-2	LOCATED INSIDE MCC
P-9	0.75"	R.G.S.	(2)#10 AWG. THHN, (1)#12 GND	P-202 POWER	PNL-2	DSC-7	LOCAL DISCONNECT SWITCH WITH CONTACTOR, INTERLOCKED WITH LS-205. RUN SIGNAL FROM MCP
P-11	0.75"	R.G.S.	(2)#12 AWG. THHN, (1)#14 GND	P-101 POWER	MCP	P-101	POWER FROM MCP
P-12	0.75"	R.G.S.	(2)#10 AWG. THHN, (1)#12 GND	MCP POWER	PNL-2	MCP	
P-13	0.75"	R.G.S.	(3)#12 AWG. THHN, (1)#14 GND	P-201 POWER	PNL-1	P-201	LOCAL MOTOR STARTER
P-14	0.75"	R.G.S.	(3)#10 AWG. THHN, (1)#12 GND	P-103 POWER	PNL-1	P-103	LOCAL MOTOR STARTER
P-15	1"	R.G.S.	(3)#8 AWG. THHN, (2)#10 GND	B-202 POWER	PNL-1	DSC-5	MOTOR STARTER IN MCC (PNL-1)
P-16	1"	R.G.S.	(3)#8 AWG. THHN, (1)#10 GND	B-201 POWER	PNL-1	DSC-6	MOTOR STARTER IN MCC (PNL-1)
P-17	1"	R.G.S.	(8)#12 AWG. THHN, (4)#12 GND	FIT-XXX POWER, JB-101 HOME RUN	MCP	FIT-XXX, JB-100	UTILIZE PULL BOX FOR FIT-XXX TEE
P-18	1"	R.G.S.	(6)#12 AWG. THHN, (3)#12 GND	FIT-103 POWER	JB-101	FIT-103	
P-19	1"	R.G.S.	(4)#12 AWG. THHN, (2)#12 GND	FIT-102 POWER	JB-101	FIT-102	
P-20	1"	R.G.S.	(2)#12 AWG. THHN, (1)#12 GND	FIT-101 POWER	JB-101	FIT-101	
C-1	1"	R.G.S.	(4)#18 AWG. SHIELDED PAIR	FIT-XXX CONTROL, JB-101C HOME RUN	MCP	JB-101C	UTILIZE SEPARATE JUNCTION BOX JB-101-C FOR CONTROLS
C-2	1"	R.G.S.	(1)#18 AWG. SHIELDED PAIR	FIT-103 CONTROL	JB-101C	FIT-103	
C-3	1"	R.G.S.	(1)#18 AWG. SHIELDED PAIR	FIT-102 CONTROL	JB-101C	FIT-102	
C-4	1"	R.G.S.	(1)#18 AWG. SHIELDED PAIR	FIT-101 CONTROL	JB-101C	FIT-101	
C-5	1"	R.G.S.	(20)#12 AWG. THHN.	P-EW-1, P-EW-2, P-EW-3, B-201, B-202 RUN CONTROL AND RUN CONDITION	MCP	PNL-1	
C-5	1"	R.G.S.	(16)#12 AWG. THHN.	AS-201/AS-202 CONTROLS (LS-201, LS-202, FS-201, FS-202, PS-XXX, PS-XXX)	MCP	JB-202	
C-7	1"	R.G.S.	(8)#12 AWG. THHN.	AS-201/AS-2-2 CONTROLS (LS-201, FS-201, PS-XXX)	JB-202	JB-201	
C-8	0.75"	R.G.S.	(4)#12 AWG. THHN.	PS-201, PS-202 CONTROL	MCP	PS-202	UTILIZE PULL BOX FOR PS-202 TEE
C-9	0.75"	R.G.S.	(2)#12 AWG. THHN.	PS-201 CONTROL	PS-202	PS-201	
C-10	0.75"	R.G.S.	(4)#12 AWG. THHN.	LS-205, P-202 CONTROL	MCP	DSC-7	

NOTES:
1. CONDUIT AND CONDUCTOR SCHEDULE DOES NOT INCLUDE HVAC, LIGHTING OR RECEPTACLES.
2. JUNCTION BOXES SHALL BE INSTALLED AS NEEDED BY THE CONTRACTOR, SUBJECT TO DESIGN CONDITIONS IN THE ELECTRICAL NOTES ON SHEET E2.


HVAC AND LIGHTING SCHEDULE						
Item	Description	Mounting	Distributor & Part Number	Quantity	Remarks	Misc.
	Light Fixtures, Process Room	Ceiling	T.B.D.	9	120 VAC	
	Light Fixture, Office	Ceiling	T.B.D.	1	120 VAC	
	Header, Process Room	Wall	T.B.D.	2	480 VAC, SEE SHEET H2	
	Sensor, Photoelectric	Wall	T.B.D.	1	120 VAC	
	Exit Sign, w/Emergency Lights	Wall	T.B.D.	1	120 VAC	
	Exhaust fan w/ Louvers	Wall	T.B.D.	1	240 VAC	
	Exterior Light	Roof	T.B.D.	1	120 VAC	




PANEL PNL-2 BREAKER SCHEDULE
SCALE: NOT TO SCALE

[illegible]


Appendix B**Construction Photographic Log**




1
Electrical pull box at
RW-1.



2
RW-1 vault and electrical
pull box



3
RW-1 Vault



4
Interior view of RW-1
vault

ARCADIS


Project Photographs
Construction
Completion Report
Agricultural Products
Division Facility
Hannibal, Missouri



5
Treatment building doors



6
Treatment building



7
 PLC control panel



8
 Circuit breaker panel

ARCADIS

Project Photographs
Construction
Completion Report
Agricultural Products
Division Facility
Hannibal, Missouri



9
Electrical breaker box



10
Heater thermostat




11
Potable water supply and
hose bib




12
Floor sump



13
Piping where recovery
well enter building



14
Piping manifold with
recovery well flow meters
and regulating valves




15

Manifold that splits flow to each air stripper, with flow meters and control valves




16

Outfall piping through floor



17
Clean-in-place piping
header and control valves



18
Clean-in-place tank and
pump

ARCADIS

Project Photographs
Construction
Completion Report
Agricultural Products
Division Facility
Hannibal, Missouri



19
Safety Shower



20
Air stripper 2



21
Air stripper 2 and blower
equipment



22
Treatment building door
and louvered vent



23
West side of treatment
building



24
Piping cleanout, showing
bollards

ARCADIS

Project Photographs
Construction
Completion Report
Agricultural Products
Division Facility
Hannibal, Missouri



25
Trenching toward outfall



26
Outfall at ditch south of
treatment building



27
Outfall, showing riprap




28
West side of treatment
building, showing
electrical transformer



29

View of graded trench
north of treatment
building



30


Flow splitting header,
showing flow meters and
control valves



31
Access steps to clean-in-
place tank




32
Air stripper 1




33
Air stripper 1



34
Bag filter prior to air
stripper 2



35
 Monitoring Screen,
 showing sump levels and
 blower pressure




36
 Monitor screen, showing
 recovery pump flows



37
 Monitor screen, showing
 clean-in-place equipment



38
 Blower and bag filter for
 air stripper 1



39
Bag filters prior to GAC
treatment



40
Portion of GAC header,
showing slip-stream
piping for Inficon GC

ARCADIS

Project Photographs
Construction
Completion Report
Agricultural Products
Division Facility
Hannibal, Missouri




41
GAC piping header



42
GAC vessels

ARCADIS

Project Photographs
Construction
Completion Report
Agricultural Products
Division Facility
Hannibal, Missouri



43

"burp lines" to remove air
from GAC vessels


Appendix C

As-Built Survey – Piping and Primary Structures

SKETCH OF SURVEY **WATER EXTRACTION SYSTEM AT HANNIBAL BASF PLANT** **MARION COUNTY, MISSOURI** (AS MADE FOR USA ENVIRONMENT, LP)

DESC	NORTHING	EASTING	ELEV.
MON #3	8629.88	4900.03	468.57
MON #4	8566.43	4445.30	470.11
MON #5	8409.58	6307.75	470.19
MON #6	8778.28	7235.35	469.38
CEN. RW-1	7775.732	6726.574	
CEN. RW-2 WELL PIT	8785.802	6074.348	
CEN. RW-3 WELL PIT	8563.975	5619.177	
NW COR. BUILDING	8314.801	5694.170	
SW COR. BUILDING	8277.227	5694.547	
SE COR. BUILDING	8277.949	5728.566	
NE COR. BUILDING	8315.523	5728.189	
CEN. TRANSFORMER PAD	8282.848	5680.292	
POWER POLE	7757.726	5362.907	
CO-02	8565.886	6076.216	
CO-03	8455.717	5814.428	
CO-05	8437.857	5814.065	
CO-07	7789.283	6496.760	
CO-08	7787.148	6102.042	
CO-09	7963.969	5857.273	
CO-10	8129.717	5660.383	
PB-01	8540.050	6071.417	
PB-02	8443.348	5819.999	
PB-03	8437.942	5820.446	
PB-04	8034.424	5766.548	
PB-05	7893.446	5978.183	
PB-06	7789.574	6176.546	
PB-07	7791.990	6443.953	
WATER METER	8100.362	5666.332	
END OUTFALL PIPE	7528.588	5504.499	
"4" PVC CLEANOUT	8438.748	5872.313	

COORDINATES AS PER ORIGINAL PLANT COORDINATES




GRAPHIC SCALE
 100 0 50 100 200
 (IN FEET)
 1 inch = 200 ft.
Legend

- Monument
- ⊗ Cleanout
- ⊕ Electric Pull Box
- UE --- Underground Electric
- ⊕ Power Pole
- Guy Wire
- - - Piping Trenches

THIS IS A RESULT OF MY SURVEY AS PREPARED UNDER MY DIRECT SUPERVISION DURING AUGUST, 2010, WHICH I CERTIFY TO BE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Kevin L. Bock 12/1/10
 KEVIN L. BOCK, PLS 2008000714



MECO ENGINEERING COMPANY, INC.
 ENGINEERS • SURVEYORS
 3120 HIGHWAY W
 HANNIBAL, MISSOURI 63401
 (573) 221-4048
 MISSOURI SURVEY LICENSE #000186

DRAWN KB	CHECKED KB
Fd. Bk. - 1059A	
Pg. - 39	
DRAWING NAME 102236	
PROJECT NO. 102-236	



Appendix D

Recovery Well Completion Logs

ARCADIS

Sample/Core Log

Boring/Well	RW-1	Project/No.	KC001589.0001.0101		Page	1	of	2
Site Location	Hannibal - Northeast corner of Richland Bldg		Drilling Started	1500 12/6/2009	Drilling Completed	1500 12/7/2009		
Total Depth Drilled	52	Feet	Hole Diameter	12	inches	Type of Sample/ Coring Device	Continuous	
Length and Diameter of Coring Device	10 feet by 7 inches				Sampling Interval	10 feet		
Land-Surface Elev.	467	feet	<input type="checkbox"/> Surveyed	<input checked="" type="checkbox"/> Estimated		Datum	Ground	
Drilling Fluid Used	Plant Potable Water				Drilling Method	Rotasonic		
Drilling Contractor	Boart Longyear				Driller	Darren Kern	Helper	Jerry Beardmore
Prepared By	Larry Benolkin				Hammer Weight	NA	Hammer Drop	NA ins.

Sample/Core Depth (feet below land surface)		Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 Inches	Sample/Core Description
From	To			
Surface	5	0	NA	Air-knifed to clear utilities - Not recovered
5	7	2.2	NA	CL -CLAY, very dark grey 10YR(3/1), stiff, medium plastic, some dark yellowish brown 10YR(4/4) mottles, no odor, no PID response, moist, not bedded
7	17	10	NA	CL, as above; at 12 feet grades to CH - Silty CLAY, very dark grey 10YR(3/1), mottled with dark yellowish brown 10YR(4/6), soft, plastic, wet, no odor, no PID response, no apparent bedding; at 15 feet, grades to SC - Clayey, Silty SAND, very dark grey 10YR(3/1), very fine to fine grained in clayey, silty matrix, medium dense, slight organic odor, trace rootlets, wet, no PID response, no apparent bedding; at 16 feet, sharp gradation to SP - SAND, olive brown 2.5Y(4/3), fine to medium grained, well sorted, rounded, loose, wet, no odor, no PID response, no apparent bedding; at 16.5 feet, abrupt change to MH - Clayey SILT, dark grey 10YR(4/1), soft, slightly plastic, wet, no odor, no PID response, very fine beds
17	27	6	NA	SW - SAND, olive brown 2.5Y(4/3), fine to medium grained, 10% silt, poorly sorted, rounded, loose, wet, no odor, no PID response; at 21 feet, grades to SP - SAND, grey 5Y(5/1), fine to medium grained, some coarse in 1/2 inch partings, well sorted, rounded, loose, wet, no odor, no PID response; likely lost sample from 23-27 feet bgs
27	37	10	NA	SP, SAND, dark grey 5Y(4/1), medium grained, some coarse, well sorted,

ARCADIS

Sample/Core Log (Cont.d)

Boring/Well

RW-1

Page 2 of 2

Prepared by


Larry Benolkin

Sample/Core Depth (feet below land surface)		Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 Inches	Sample/Core Description
From	To			
				rounded, loose, wet, no odor, no PID response, no apparent bedding; at 33
				feet, abrupt change to GW - Sandy GRAVEL, dark grey 5Y(4/1), rounded to
				subangular gravel up to 5 inches, predominantly chert and limestone, clast-
				supported, 10-15% medium to coarse sand as above; at 35 feet, abrupt change
				to SM - Silty SAND, dark grey 5Y(4/1), some olive brown 2.5Y(4/4), fine to
				medium grained with 20% silt, poorly sorted, rounded, loose, wet, no odor,
				no PID response, no apparent bedding; at 36 feet, abrupt change to SW - SAND
				with Gravel, grey 5Y(5/1), fine to coarse grained, with 20% rounded gravel up
				to 1.5 inches, poorly sorted, rounded, loose, wet, no odor, no PID response
37	47	8	NA	SW, as above; at 37.5 feet, grades to GW, GRAVEL with Sand, olive brown
				2.5Y(4/3), rounded to subangular gravel up to 4 inches in matrix of medium to
				coarse sand, poorly sorted, loose, wet, no odor, no PID response, no apparent
				bedding; at 38.5 feet, abrupt change to SP - SAND, grey 5Y(5/1), fine grained,
				well sorted, rounded, loose, wet, no odor, no PID response, no apparent
				bedding; at 40.5 feet, abrupt change to SW - SAND with Gravel, olive brown
				2.5Y(4/3), medium to coarse grained, rounded, poorly sorted, with 30%
				rounded gravel up to 1.5 inches, loose, wet, no odor, no PID response; at 42
				feet, grades to SP - SAND, olive brown 2.5Y(4/3), medium grained, well sorted
				no odor, no PID response, no apparent bedding; lost sample 45-47 feet bgs
47	52	0	NA	Lost sample

ARCADIS

Well Construction Log

(Unconsolidated)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.

* Depth Below Land Surface

Project Wyeth Well Installation
KC001589.0001.00100 Well RW-1

Town/City Hannibal, MO

County Marion State MO

Permit No. _____

Land-Surface (LS) Elevation and Datum:

467 feet ☐ Surveyed

☒ Estimated

Installation Date(s) 12/06-07/2009

Drilling Method Rotosonic

Drilling Contractor Boart Longyear

Drilling Fluid Potable water

Development Technique(s) and Date(s)

Fluid Loss During Drilling ~1200 gallons

Water Removed During Development _____ gallons

Static Depth to Water _____ feet below M.P..

Pumping Depth to Water _____ feet below M.P.

Pumping Duration _____ hours

Yield _____ gpm Date _____

Specific Capacity _____ gpm/ft

Well Purpose Groundwater recovery

Remarks _____

Prepared by Larry Benolkin

ARCADIS

Sample/Core Log

Boring/Well RW-2 Project/No. KC001589.0001.0101 Page 1 of 2

Site Location Hannibal - Northeast corner of Richland Bldg Drilling Started 930 12/5/2009 Drilling Completed 12/6/2009

Total Depth Drilled 47 Feet Hole Diameter 12 inches Type of Sample/ Coring Device Continuous

Length and Diameter of Coring Device 10 feet by 7 inches Sampling Interval 10 feet

Land-Surface Elev. 470 feet ☐ Surveyed ☒ Estimated Datum Ground

Drilling Fluid Used Plant Potable Water Drilling Method Rotosonic

Drilling Contractor Boart Longyear Driller Darren Kern Helper Jerry Beardmore

Prepared By Larry Benolkin Hammer Weight NA Hammer Drop NA ins.

Sample/Core Depth (feet below land surface)		Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 Inches	Sample/Core Description
From	To			
Surface	5	0	NA	Air-knifed to clear utilities - Not recovered
5	7	2.5	NA	CL -C LAY, dark olive grey 5Y(3/2), stiff, medium plastic, trace bricks and some subangular limestone gravel, moist, no odor, no PID response, no apparent bedding, FILL
7	17	11.5	NA	CL, Silty CLAY, dark olive grey 5Y(3/2), some dark yellowish brown 10YR(4/4) mottling, stiff, medium plastic, moist, no odor, no PID response, no apparent bedding; at 9.5 feet grades to CL - Silty CLAY, dark olive grey 5Y(3/2) mottled with yellowish brown 10YR(5/6), some 1/4 inch black concretions, medium stiff, medium plastic, moist, no odor, no PID response, not bedded; at 13 feet, grades to SC - Clayey SAND, olive grey 5Y(5/2) mottled with olive brown 2.5Y(4/6), very fine to fine grained, poorly sorted within clayey matrix, very soft, slightly plastic, wet, slow dilatancy, no apparent bedding, no odor, no PID response; at 16 feet grades to SM - Silty SAND, dark greyish brown 2.5Y(3/2), fine to medium grained, loose, wet, well rounded, poorly sorted with silty matrix, no odor, no PID response, no apparent bedding
17	27	10	NA	SM, as above; at 18 feet abrupt change to SP, SAND,, olive brown 2.5Y(4/3), fine grained, very loose, wet, no odor, no PID response, no apparent bedding; at 19.0 to 19.3 lens of SM - Silty SAND, greyish brown 2.5Y(5/2), very fine to fine grained, 20% silt, loose, wet, no odor, no PID response; at 19.3 feet,

ARCADIS

Sample/Core Log (Cont.d)

Boring/Well

RW-2

Page 2 of 2

Prepared by


Larry Benolkin

Sample/Core Depth (feet below land surface)		Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 Inches	Sample/Core Description
From	To			
				SP, as above; at 21 feet grades to SW - well graded SAND, dark greyish brown 2.5Y(4/2), fine to medium grained, some coarse, poorly sorted, rounded, very loose, wet, no odor, no PID response, no apparent bedding
27	37	10	NA	SW, as above; at 30 feet grades to SP - SAND, grey 5Y(5/1), medium grained, some coarse, well sorted, rounded, very loose, wet, slight organic odor, no PID response, no apparent bedding; at 34 feet grades to GW - Sandy GRAVEL, grey 5Y(5/1), medium rounded gravel up to 4 inches, with 40% medium to coarse sand, loose, wet, no odor, no PID response, no apparent bedding; at 36.5 feet abrupt change to ML - SILT, olive grey 5Y(5/2), soft, non-plastic, wet, no odor, no PID response, possible very fine bedding
37	47	10	NA	GW - GRAVEL, light olive brown 2.5Y(5/3), poorly sorted subround to sub-angular gravel (predominantly chert and volcanics) 15% medium to coarse sand, loose, wet, no odor, no PID response, not bedded; at 38 feet, abrupt change to SP - SAND, light olive brown 2.5Y(5/3), medium grained, some coarse, well sorted, rounded, loose, wet, no odor, no PID response, no apparent bedding; at 38.5 feet abrupt change to GW - Sandy GRAVEL, light olive brown 2.5Y(5/3), rounded gravel up to 6 inches, poorly sorted with 50% fine to medium grained sand, loose, wet, no odor, no PID response; at 39.5 feet, grades to SW - SAND, light olive brown 2.5Y(5/3), fine to medium grained, some coarse, poorly sorted, rounded, trace of black organic matter, loose, wet, no odor, no PID response, in gross 6-inch beds, becomes medium to coarse grained below 40 feet; at 41.5 feet, grades to SW - Gravelly SAND, light olive brown 2.5Y(5/3), fine to medium grained, with 30% gravel up to 6 inches, subrounded gravel, loose, wet, no odor, no PID response, no apparent bedding; at 44 feet, abrupt change to SM - Silty Silty SAND, very dark greyish brown 10YR(4/2), very fine to fine grained, sand with silt matrix, medium dense, wet, no odor, no PID response; at 45 feet, grades to SP - SAND, light olive grey 2.5Y(5/2), fine to medium grained, well sorted, rounded, loose, wet, no odor, no PID response

ARCADIS

Well Construction Log

(Unconsolidated)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.

* Depth Below Land Surface

Project Wyeth Well Installation
KC001589.0001.00100 Well RW-2

Town/City Hannibal, MO

County Marion State MO

Permit No. _____

Land-Surface (LS) Elevation and Datum:

470 feet ☐ Surveyed

☒ Estimated

Installation Date(s) 12/05-06/2009

Drilling Method Rotosonic

Drilling Contractor Boart Longyear

Drilling Fluid Potable water

Development Technique(s) and Date(s)

Fluid Loss During Drilling ~1400 gallons

Water Removed During Development _____ gallons

Static Depth to Water _____ feet below M.P..

Pumping Depth to Water _____ feet below M.P.

Pumping Duration _____ hours

Yield _____ gpm Date _____

Specific Capacity _____ gpm/ft

Well Purpose Groundwater recovery

Remarks _____

Prepared by Larry Benolkin

ARCADIS

Sample/Core Log

Boring/Well RW-3 Project/No. KC001589.0001.0101 Page 1 of 2

Site Location Hannibal near Engineering Bldg Drilling Started 1320 12/2/2009 Drilling Completed 1520 12/4/2009

Total Depth Drilled 46 Feet Hole Diameter 12 inches Type of Sample/ Coring Device Continuous

Length and Diameter of Coring Device 10 feet by 7 inches Sampling Interval 10 feet

Land-Surface Elev. 468 feet ☐ Surveyed ☒ Estimated Datum Ground

Drilling Fluid Used Plant Potable Water Drilling Method Rotosonic

Drilling Contractor Boart Longyear Driller Darren Kern Helper Jerry Beardmore

Prepared By Larry Benolkin Hammer Weight NA Hammer Drop NA ins.

Sample/Core Depth (feet below land surface)		Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 Inches	Sample/Core Description
From	To			
Surface	5	0	NA	Air-knifed to clear utilities - No recovery
5	6	0.7	NA	CL -Silty CLAY, dark grey 10YR(4/1), medium stiff, medium plastic, moist, no odor, no PID response, no apparent bedding
6	16	11	NA	CL -Silty CLAY, dark grey 10YR(4/1) mottled with dark yellowish brown 10YR(4/6), medium stiff, medium plastic, moist, no odor, no PID response; at 12.5 feet grades to CH - Silty CLAY, dark greyish brown 10YR(4/2) mottled with yellowish brown 10YR(5/8), soft, plastic, no odor, no PID response; at 16 feet abrupt changes to SM - Silty SAND, fine to medium grained, well sorted, rounded, with silty matrix, dark grey 10YR(4/1), loose, wet, no odor, no PID response, no apparent bedding
16	26	9.5	NA	SM, as above; at 16.5 feet, abrupt change to CL- Silty CLAY, dark grey 10YR(4/1), some dark yellowish brown 10YR(4/6) mottles, stiff, medium plastic, moist, no odor, no PID response; at 16.8 feet, abrupt change to SP - poorly graded SAND, brownish grey 2.5Y(5/2), fine grained, well sorted, loose, wet, no odor, no PID response, possible 1/4 to 1/2 inch clay lens at 21 feet; at 24.5 feet abruptly grades to SP - poorly graded SAND, greyish brown 2.5Y(5/2), medium to coarse grained, moderately well sorted, sub- round to rounded, loose, wet, no odor, no PID response
26	36	9	NA	SW - well graded SAND, brownish grey 2.5Y(5/2), fine to medium grained,

ARCADIS

Sample/Core Log (Cont.d)

Boring/Well RW-3

Page 2 of 2


Prepared by Larry Benolkin

Sample/Core Depth (feet below land surface)		Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 Inches	Sample/Core Description
From	To			
				loose, poorly sorted, wet, no odor, no PID response, no apparent bedding;
				at 29 feet is a possible 1/4 inch clay lense; at 31.5 feet grades to SP -
				poorly graded SAND, brownish grey 2.5Y(5/2), medium to coarse grained,
				well sorted, loose, wet, no odor, no PID response, no apparent bedding;
				at 35 feet grades to SW - well graded SAND with gravel, brownish grey
				2.5Y(5/2), medium to coarse grained, 5-10% rounded gravel up to 2 inches,
				gravel is predominantly basalt and some limestone, loose, wet, no odor,
				no PID response
36	46	10	NA	SW - SAND with gravel as above; at 37 feet grades to GW - Gravel with sand,
				limestone and volcanics rounded gravel up to 6 inches in matrix of fine to
				medium grained sand, brownish grey 2.5Y(5/2); at 38.5 feet grades to SP -
				poorly graded SAND, light olive grey 2.5Y(5/4), well sorted, 5% gravel up
				to 1 inch, loose, wet, no odor, no PID response; at 41 feet grades to SP -
				poorly graded SAND, fine to medium grained, well sorted, loose, wet, no
				odor, no PID response, no apparent bedding; at 42 feet abrupt change to
				SP - poorly graded SAND, olive brown 2.5Y(4/3), fine to medium grained,
				well sorted, in first 6 inches black vitreous concretions up to 4 inches, loose,
				wet, no odor, no PID response, no apparent bedding; at 44 feet abrupt
				change to SP - poorly sorted SAND, yellowish red 5YR(4/6), fine grained,
				well sorted, loose, wet, no odor, no PID response, no apparent bedding

ARCADIS

Well Construction Log

(Unconsolidated)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.

* Depth Below Land Surface

Project Wyeth Well Installation
KC001589.0001.00100 Well RW-3

Town/City Hannibal, MO

County Marion State MO

Permit No. _____

Land-Surface (LS) Elevation and Datum:

468 feet ☐ Surveyed

☒ Estimated

Installation Date(s) 12/02-04/2009

Drilling Method Rotosonic

Drilling Contractor Boart Longyear

Drilling Fluid Potable water

Development Technique(s) and Date(s)

Fluid Loss During Drilling ~1400 gallons

Water Removed During Development _____ gallons

Static Depth to Water _____ feet below M.P..

Pumping Depth to Water _____ feet below M.P.

Pumping Duration _____ hours

Yield _____ gpm Date _____

Specific Capacity _____ gpm/ft

Well Purpose Groundwater recovery

Remarks _____

Prepared by Larry Benolkin